

## Holland Haven Seawall Frontage, Holland-on-Sea

Coast Protection works to reinforce and improve a section of seawall below the Gunfleet Boating Club at Holland Haven, Holland-on-sea is now complete.

Holland Haven Gunfleet Boating Club Frontage before works commenced



Work completed June 2011



The work consisted of removing a section of the corroding sheet pile at the top of the structure and replacing it with new precast concrete units. Also included was a new piled toe together with protective rock armour to support the existing structure. The length of seawall that has been improved is approximately 80 metres.

The project commenced in November 2010 and was completed in June 2011.

The project was managed by Technical and Procurement Services on behalf of the Technical Services Portfolio Holder, and was funded by DEFRA through the Environment Agency.

The consulting engineers for the scheme were [Haydn Evans Consulting](#) of Ipswich, Suffolk.

The CDM Co-Ordinators were [Daniel Connal Partnership](#) of Colchester, Essex.

The contractor for the work was [J Breheney Contractors Limited](#) of Ipswich, Suffolk.