

## Queensway Seawall Emergency Works, Holland on Sea

Repair work to the seawall below Queensway, Holland on Sea, commenced on Monday 26th February 2007. This section of wall had suffered damage during the prolonged period of stormy weather experienced in January and the repairs stabilised and reinforced the damaged area.



The work included:

- Stabilising the existing structure with piling to pin the existing wall in place
- Constructing a new steel piled footing and stepped concrete seawall on a new line in front of the existing wall
- Reconstructing the promenade





The work was completed on 10th August 2007.



This was a challenging project but due to good co-operation and joint working between the contractors J Breheny Contractors Limited from Creting St Mary, Suffolk, [www.breheny.co.uk](http://www.breheny.co.uk) and Tendring District Council the project has been successfully completed.