

York Road Sea Defence, Holland-on-Sea

Coast Protection works to reinforce and improve a section of seawall below York Road, Holland on Sea commenced in September 2009.

[York Road location plan](#)



York Road seawall before works commenced.



Completed works (May 2010)

The improvements consisted of driving new steel sheet piles to provide a footing in front of the existing wall and constructing a new stepped seawall in front of the old wall supported by this footing. The length of seawall which has been improved is approximately 68 metres.

The promenade has been resurfaced and the beach café access has been upgraded.

The project was managed by Technical and Procurement Services on behalf of the Technical Services Portfolio Holder, and was funded by DEFRA through the Environment Agency.

The contractor for the work was [J Breheny Contractors Limited](#) of Creeting St Mary, Suffolk

The consulting engineers for the scheme were [Haydn Evans Consulting](#) of Ipswich, Suffolk

The CDM Co-Ordinators were [Daniel Connal Partnership](#)